



REVISIONS

NO.	DATE	DESCRIPTION
1	2/09	ADDED NOTE
2	3/10	ADDED NOTE

DETAIL "A"
N.T.S.

- NOTES:
1. A 14 GAUGE INSULATED SOLID COPPER WIRE SHALL BE LAID ON TOP OF THE PVC PIPE TO AID IN LOCATING THE PIPE FOR MAINTENANCE PURPOSES. THE WIRE SHALL BE SECURED TO THE PIPE WITH DUCT TAPE NEAR EVERY BELL AND AT THE CENTER OF EACH PIPE JOINT. THE WIRE SHALL BE FASTENED SECURELY TO A CAST IRON FITTING AT EACH MAIN LINE VALVE AND FIRE HYDRANT AND TO SERVICE LINES AS DIRECTED BY THE SCDHEC (R:61-58.4D.(11)(G) AND YORK COUNTY SPECIFICATIONS.
 2. SERVICE LINE FROM THE UPSTREAM SIDE OF THE VALVE TO METER BOX MUST BE ENDOPURE ASTM D 2239, SDR7, PC 200
 3. NO HALF-SIZES ALLOWED FOR THE SERVICE LINE FROM MAIN TO METER BOX.

**YORK COUNTY
ENGINEERING
STANDARDS**

**SERVICE CONNECTION
1.5" & 2" METER**

STD. NO.
11.19
DATE
09/06