



NOTES:

1. BACKFLOWS MUST CONFORM TO STATE & LOCAL SPECIFICATIONS.
2. APPROVED BACKFLOW INCLUDES SHUT OFF VALVES #1 & #2 AS PART OF THE UNIT. NO SUBSTITUTIONS SHALL BE PERMITTED. 6" CLEARANCE SHALL BE WITH VALVE OPEN.
3. VAULT, DOORS, OR COVERS AND SUPPORT ASSEMBLY SHALL BE DESIGNED PER CURRENT YORK COUNTY SPECIFICATIONS.
4. TEST COCK #1 SHALL BE UPSTREAM OF SHUT OFF VALVE#1 AND IS PART OF ASSEMBLY.
5. IF DRAINAGE CANNOT BE PROVIDED TO FREE ATMOSPHERE OR STORM DRAINAGE, THE BACKFLOW SHALL BE INSTALLED ABOVE GROUND.
6. FLOOR AND JACK STANDS TO BE DESIGNED BY OWNER.
7. ALL TESTING MUST BE DONE BY A STATE CERTIFIED BACKFLOW PREVENTION TESTER.
8. INITIAL BACKFLOW DEVICE TEST REPORT MUST BE SUBMITTED TO YORK COUNTY PRIOR TO METER ACTIVATION.

REVISIONS

NO.	DATE	DESCRIPTION
1	05/16	ADDED NOTE 6

**YORK COUNTY
ENGINEERING
STANDARDS**

DOUBLE CHECK VALVE ASSEMBLY
3" – 10" BELOW GROUND

STD. NO.	11.22
DATE	04/09